BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/04/2014-15 Dated: 31-10-2014

APPROVED TENDER SCHEDULE –'B'

Item No: 33

Name of Work:-Improvements to drains at Puttenahalli KHB colony in ward No-02 of yelahanka Sub division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri SHIVAKUMAR N	
				Rate	Rate in Words
1	KSRR 300-1 Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed. the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH chapter 3 No. 156/ Item No. 19.1/ PWD SR 2014-15	Cum	24.18	75.00	Rupees seventy five only
2	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.2.5, No. 5/ Item No. 2.3/ PWD SR 2014-15	Cum	24.02	176.00	Rupees one hundred seventy six only
3	KSRB 100-1 Loading and unloading of stone aggregates / sand/ kankar/ Moorum /soil KSRRB M100-1 Placing lipper at loading with front end loader dumping turning for return trip excluding time for haulage and return trip complete as per specification Item No 17.1 page 150 and KSRB M.100.4.1 cost of haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 150 (SR 2014-15)	Cum	48.16	79.00	Rupees seventy nine only
4	KSRRB M300-5: construction of embankment with approved material gravel/murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement table 300-2 complete as per specifications. (which includes cost of gravel/murrum, watering charges & compaction by vibratory roller) MORTH specification Page No. 305.4.3. No. 144/ Item No. 19.6/ PWD SR 2014-15	Cum	18.75	220.00	Rupees two hundred twenty only
5	KSRB-4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement at 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.86cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, Specification No. KBS II.1.4.2, No. 12/ Item No. 4.2/ PWD SR 2014-15	Sqm	24.03	5064.00	Rupees five thousand sixty four only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri SHIVAKUMAR N	
				Rate	Rate in Words
6	KSRRB M600-G cement concrete pavement, construction unreinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with 43 grade cement or any other type as per clause 1051.2.2M20/M30 at 360/450 kg per cum, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25mm, mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including leveling the form work as per drawing,i, spreading the concrete with shovels, rackers compacted using needle, scred and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sclant primer, joint sealant, admixtures as approved curing compound, finishing to lines and grade as per drawing complete as per specification M30(at 360kg per cum coarse aggregate @ 0.69cum and fine aggregare @	Sqm	16.05	5896.00	Rupees five thousand eight hundred ninety six only
7	Vaccum De- writing with vacuum pump and suction mat and compaction with skin finish dubbed with floating disc including cost of generator, HOM of machinery Screed Vibratory Power Floatersblade and disc etc. with all lead and lift. Page No 171 Item No 22.7 SR 2014-15	Cum	160.10	97.00	Rupees ninety seven only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64